

## WALL ANGLE O° UNREINFORCED

## **NOTES:**

- 1. Maximum allowable height (H) = 2'-8" \*
- 2. Erect wall in 8" increments and backfill after each stage.
- 3. Design based on equivalent soil fluid weight = 30 pcf and block weight = 130 pcf.
- 4. For taller walls or conditions with surcharge consult geogrid reinforcement section. (Dwg's 5-S2 thru 7-S2)
- 5. For conditions with water runoff, positive discharge drain pipe must be provided.

WALL SECTION

O° BATTER

TERRASTOP™ SYSTEM 2

RAPID BUILDING SYSTEMS

P.O. Box 3335 Reston, VA 20195 - USA

SCALE: NONE

PROJECT: 99601

DRAWING: 1 - S2